

**VIDYA INTERNATIONAL CHARITABLE TRUST
THALAKKOTTUKARA**

NAME OF WORK: Construction of 3.0 m Culvert over Vazhani Irrigation canal at Kurumal owned by Sreekkutti and Sreedevi, Pattiath House, Velur in Velur Panchayath Sy. No. 634/1P

QUOTATION NOTICE

Date: 21-07-2020

Sealed Competitive Quotations in the prescribed format are invited from experienced and established suppliers/contractors for the works described below. All terms and Conditions pertaining to the quotation should invariably be furnished at the first instance itself. Documents if any to prove authentic representation of the product/work quoted and previous experience in the field may be attached along with the quotation.

Terms & Conditions

A	Last Date of Receipt	30-07-2020
B	EMD	0
C	Validity	30 days
D	Price	Inclusive of GST and all other Taxes
E	Delivery Period / Period of Completion	2 Weeks
F	Guarantee	1 Year.
G	Payment Terms	After satisfactory completion of work and verification
H	Agreement	Agreement to be executed in stamp paper worth Rs.200/-
I	Security Deposit	5% of contract value by DD/Remittance at the bank A/c
J	Invoice	To be prepared in favour of The Executive Director, VICT, Thrissur
K	Bank Charges	At contractor's Account



EXECUTIVE DIRECTOR



Executive Director
Vidya International Charitable Trust

CONTACT No: 94 4766 8547

**VIDYA INTERNATIONAL CHARITABLE TRUST
THALAKKOTTUKARA**

NAME OF WORK: Construction of 3.0 m Culvert over Vazhani Irrigation canal at Kurumal owned by Sreekutty and Sreedevi, Pattiath Hc
Velur in Velur Panchayath Sy. No. 634/1P

SCHEDULE TO THE QUOTATION

Sl.No.	Description	Quantity						Amount	
		Unit	No	Length	Breadth	Height	Total	Rate	Amount
1	Earth work excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sq.m on plan) including getting out and disposal of earth lead up to 50 m and lift upto 1.5 m, as directed by Engineer-in-charge (2-6-1)	M ³	2	5.20	1.50	3.50	54.60		
2	Cement concrete 1:3:6 (1 cement, 3 sand and 6 broken stones) using 40 mm broken stone for footing below retaining wall including cost and conveyance of materials, labour charges and watering for curing etc... 1) Footing 2) retaining wall	M ³ M ³ M ³	2	5.20 5.00	1.50 0.975	0.20 3.50	3.12 34.13 37.25		
3	Providing and laying in position specified cement concrete (cast-in-situ) 1:1.5:3 (1 cement, 1.5 coarse sand and 3 graded stone aggregate 20 mm nominal size) for all RCC works upto plinth level including the cost and conveyance of materials and labour, shuttering, curing etc. complete but excluding cost of reinforcement. 1) Slab 2) Hand Rail	M ³ M ³ M ³	1 2	6.00 6.00	3.00 0.75	0.25 0.10	4.50 0.90 5.40		
4	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete upto plinth level using thermo- mechanically treated bars.	Kg					648.0		
Total									

(Rupeesonly)

[Signature]

Executive Director

Executive Director
Vidya International Charitable Trust



Contractor